DDS- Planning & Zoning: Historic Review Application



Submission date:	
Receipt number:	

13 April 2021, 1:24PM 184

Property Information

Property Address	Street: 29 Mather street City: Hartford State: CT Zip Code:)6120
Zoning District:	
Parcel ID:	
Property Owner:	Romaine Reid
Property Owner's Address:	Street: 86 Mather st 3rd fl City: Hartford State: CT Zip Code: 06120
Phone:	860 690 4424
Email:	rlrhcs@gmail.com

Applicant

Please check if "Applicant" is the same as "Property	Please check if "Applicant" is the same as "Property
Owner"	Owner"
Name of Applicant:	
File Date:	

Address:	Street: City: State: Zip Code:
Phone:	
Email:	
Primary Point of Contact	
Name:	Romaine Reid
Phone:	860 690 4424

Email:

rlrhcs@gmail.com

Describe your application action(s) and provide as much **PROJECT NARRATIVE**:

detail as possible.

• Windows:

I will be removing all the current vinyl window frames because all the window panes and sashes of missing. I will be replacing them with crystal series 100 vinyl double hang replacement windows. Specs of the windows is attached.

• Front porch:

I will be removing the plywood used for floor decking, rotted floor joists, concrete steps and cinder blocks footings and bringing the deck up to code with by replacing them with 12" tube and 42" deep concrete footings, 1x6 PT decking boards, 2x4 PT with 1x1 baluster for the railings, 2x8 PT floor joists and 2x12 PT stringers terminated on the concrete for the stairs.

• Rear porch/deck:

I will be removing the plywood used for the floor decking and replacing it with 1x6 PT decking boards. I replacing the missing rails on the deck with 2x4 PT with 1x1 baluster for the railings.

Decking material to be used: Flooring- 1x6 PT decking board Screws- 2 ¹/₂" exterior decking screws Floor joist- 2x8 PT Railings- 2x4 PT and 1x1 PT balusters Footings- 12" tube, concrete mix Post- 6x6 PT and 4x4 PT

Proposed work:	Demolition Repairs
Current materials being repaired/replaced:	rotted 2x6 floor joists, cinder blocks footings, plywood used for floor decking
Materials/products being used in work:	2x8 PT floor joist, 12" tube with concrete for footings, 1x6 PT floor decking board, 2x4 PT railings and 1x1 PT balusters, vinyl double hang windows

 Please upload all supporting materials and photographs
 Zoning Application.docx

 below.
 window specs.pdf

IMG-20210412-WA0025[1].jpg IMG-20210412-WA0024[1].jpg IMG-20210412-WA0023[1].jpg IMG-20210412-WA0021[1].jpg IMG-20210412-WA0018[1].jpg IMG-20210412-WA0018[1].jpg IMG-20210412-WA0025[1].jpg IMG-20210407-WA0019[1].jpg IMG-20210407-WA0020[1].jpg IMG-20210407-WA0023[1].jpg IMG-20210407-WA0024[1].jpg IMG-20210407-WA0025[1].jpg IMG-20210407-WA0029[1].jpg IMG-20210407-WA0030[1].jpg IMG-20210407-WA0036[1].jpg IMG-20210407-WA0023[1].jpg

Signatures

Signature of Applicant:



Link to signature

Name of Applicant:

Date:

Signature of Property Owner:

Romaine Reid

4/13/2021

Link to signature

Name of Property Owner:

Date:

Romaine Reid

4/13/2021



Customer Info: Romaine Reid 86 Mather Street Hartford, CT 06120

PROJECT ADDRESS: 29 MATHER STREET, HARTFORD, CT 06120

PROJECT NARRATIVE

• Windows:

I will be removing all the current vinyl window frames because all the window panes and sashes of missing. I will be replacing them with crystal series 100 vinyl double hang replacement windows. Specs of the windows is attached.

• Front porch:

I will be removing the plywood used for floor decking, rotted floor joists, concrete steps and cinder blocks footings and bringing the deck up to code with by replacing them with 12" tube and 42" deep concrete footings, 1x6 PT decking boards, 2x4 PT with 1x1 baluster for the railings, 2x8 PT floor joists and 2x12 PT stringers terminated on the concrete for the stairs.

• Rear porch/deck:

I will be removing the plywood used for the floor decking and replacing it with 1x6 PT decking boards. I replacing the missing rails on the deck with 2x4 PT with 1x1 baluster for the railings.


Decking material to be used:

Flooring- 1x6 PT decking board Screws- 2 ¹/₂" exterior decking screws Floor joist- 2x8 PT Railings- 2x4 PT and 1x1 PT balusters Footings- 12" tube, concrete mix Post- 6x6 PT and 4x4 PT

1

Preferred by Contractors

CRYSTAL SERIES 100




Features

- Mechanical Fastened Frame & Sashes
- Strong Multi-Chamber Construction
- Frame Depth: 3-1/4"
- Insulating Glass Unit Depth: 7/8"
- Low-E Coated Glass
- Argon Filled IGU
- PPG Intercept "Warm Edge" Spacer
- Tilting Sashes for Easy Cleaning
- Constant-Force Balance System
- Insulating Exterior Foam Wrap
- Dual Ventilation Latches
- Integral Extruded Lift Handle
- Jamb Adjusters
- Half Screen Included
- Lifetime Limited Warranty

Options

Special Grid Patterns



Crystal Window & Door Systems, Ltd.

 NYC, NY (HQ)
 31-10 Whitestone Expressway, Flushing, NY 11354
 Tel: 800.472.9988/718.961.7300
 Fax:718.460.4594

 SCRANTON, PA
 204 Franklin Valley Rd, Benton, PA 18414
 Tel: 570.276.8000
 Fax: 570.563.5313

 CLEVELAND, OH
 29299 Clemens Rd. 1-B, Westlake, OH 44145
 Tel: 440.871.8694
 Fax: 440.871.8690

 ST. LOUIS, MO
 300 Axminister Dr., Fenton, MO 63026
 Tel: 636.305.7880
 Fax: 636.305.7881

 CHICAGO, IL
 1300 W. 35th st. Chicago, IL 60609
 Tel: 773.376.6688/888.280.3288
 Fax: 773.376.6868

Follow us on:





TM

2016-2017 Crystal Window & Door Systems, Ltd. All Rights Reserved. Printed in USA































